

From Vision to Reality: **A Case Study in Integrated Project Delivery**



Introductions



Aislinn Nagy,
DBIA, LEED AP BD+C
Education Market Leader



Jessica Ligator,
PMP, LEED AP
Director of Project
Development



Nihal Haddad Alwakeel,
AIA, NCARB,
LEED AP BD+C
Senior Design Manager

Agenda

1. What is Integrated Project Delivery
2. Identifying Project Risks
3. Recent Market Challenges
4. Case Study



AIA CES Provider Statement

HASKELL is a registered provider of AIA-approved continuing education under Provider Number **C500**. All registered AIA CES Providers must comply with the AIA Standards for Continuing Education Programs. Any questions or concerns about this provider or this learning program may be sent to AIA CES (cessupport@aia.org or (800) AIA 8837, Option 3).

This learning program is registered with AIA CES for continuing professional education. As such, it does not include content that may be deemed or construed to be an approval or endorsement by the AIA of any material or construction or any method or manner of handling, using, distributing or dealing in any material or product.

AIA continuing education credit has been reviewed and approved by AIA CES. Learners must complete the entire learning program to receive continuing education credit. AIA continuing education Learning Units earned upon completion of this course will be reported to AIA CES for AIA members. Certificates of Completion for both AIA members and non-AIA members are available upon request.



From Vision to Reality: A Case
Study in Integrated Project
Delivery - AIA Course




Survey Question



Integrated Project Delivery



What is Integrated Project Delivery?



What is Integrated Project Delivery?

Key Difference is Timing of Builder Involvement

Design-Bid-Build

Select Architect	Planning	Preliminary Design	Final Design	Permit	Cost	Construction
				Select GC	Established	


Design-CMAR

Select Architect	Planning	Preliminary Design		Final Design	Construction
	Select CM	Cost Estimates	Cost Establish	Permit	


Design-Build

Select Design-Builder	Planning	Preliminary Design	Final Design	Construction
	Cost Estimates	Cost Establish	Permit	

Influence Over Costs




Integrated Project Delivery Myths



Early Builder
Engagement Reduces
Price Competition

Factors Beyond Price
Lead to Favoritism
during Award




Owner Loses Control
of the Project Design



Choosing the Best Delivery Approach

Integrated Project Delivery

- ♦ Reduces Construction Fees & Cost
- ♦ Reduces Design Cost
- ♦ Shortens Project Timeline
- ♦ Improves Access to Materials
- ♦ Eliminates Layers of Markup
- ♦ Increases Coordination Effort/Risk



Design Assist with Integrated Project Delivery

Design Assist engages vendors or SMEs during the design phase to streamline construction, reduce costs, and improve quality


- ♦ Preferred/Proprietary Providers
- ♦ Existing & Under Warranty Systems Providers
- ♦ Recognized Subject Matter Experts
- ♦ Local & OEO Suppliers
- ♦ May Reduce Competition During Bidding Period



Benefits of Early Procurement

Cost savings, reduced risk of delays, ensures items are available when needed, and avoid potential delays and cost overruns.

- ♦ Removes Material from Critical Path
- ♦ May Eliminate Layers of Markup
- ♦ May Reduces Inventory & Training Cost
- ♦ May Increase Local & OEO
- ♦ Improves Parity & Equity
- ♦ May Add Storage & Warranty Extension Cost





Identifying Project Risks


Typical Project Risks



Site Conditions



Cost Control



Scheduling



Construction Documents
Coordination



AHJ / Permitting



Market Input

Risk Mitigation Strategies

1

Understand and Identify Risks

Identifying potential risks to your project by reviewing past projects, collaborating with stakeholders, conducting brainstorming sessions, etc.

2

Assess Identified Risks

Collaborating with team members to analyze the identified risks and determine which ones are most likely to occur and how large of an impact they would have on the project.

3

Create Mitigation Plan


Creating an actionable plan on how to mitigate each of the identified risks with a focus on the most likely to occur and greatest impact.

4

Monitor and Control Risks

Monitoring the status of each risk throughout design and construction and updating the mitigation action plan. This includes adding new risks as they are identified and new mitigation strategies.

Recent Market Challenges



Integrated Delivery Solution

- ♦ Engage Key Subs Early to Lock in Labor Commitments
- ♦ Attract Subs from Other Markets
- ♦ Engage Labor Force Directly about Project



Materials

- ♦ Lead Times

Collaborative Delivery Solution

- ♦ Tracking Current Trends
- ♦ Communicating Challenges Early
- ♦ Alternate Materials/Equipment
- ♦ Early Procurement Strategies
- ♦ Communicate directly with vendors


MATERIAL LEAD TIMES IN WEEKS			
Description	Material Lead Time	Contract and Submittal	Total Lead Time
262400 Switchboards Average	72	10	82
262300 Low-Voltage Switchgear Average	59	10	69
261200 Medium Voltage Transformers Average	62	6	68
263200 Generator Average	56	8	64
236400 Packaged Water Chillers Average	44	10	54
072200 Polyiso Insulation Average	45	6	51
133419 Pre-Engineered Metal Buildings Average	34	16	50
262416 Distribution Panelboards Average	40	10	50
237400 RTU Average	39	10	49
142000 Elevators - Traction Average	33	12	45
237300 Air Handler Unit Average	33	10	43
262200 Low-Voltage Transformers Average	32	10	42
262416 Panelboards Average	29	10	39
236500 Cooling Towers Average	28	10	38
114000 Kitchen Equipment Average	25	12	37
072216 Coverboard Average	30	6	36
412213.13 Bridge Cranes Average	27	8	35
081400 Wood Doors Average	25	10	35
061600 Exterior Sheathing Average	26	8	34
084513 Polycarb Panels Average	26	8	34
235200 Boilers Average	26	8	34
074213 Insulated Metal Panels Average	25	8	33
084300 Aluminum Storefront Average	21	12	33
230920 VFDs Average	25	8	33
221123 Booster Pump Average	24	8	32

Inflation


- ◆ Driven by Material Shortages
- ◆ Affected all Sectors

Integrated Delivery Solution

- ◆ Forecasting and Appropriate Budgeting
- ◆ Alternate Materials/Equipment
- ◆ Early Procurement Strategies



Case Study



Case Study



Jacksonville University Athletic Complex

Jacksonville University

Jacksonville University envisioned replacing their existing outdated pool facility and create a new Athletic Complex with resort-style amenities.

(New Resort Style Pool with Sun Deck, Beach Volleyball courts, Amenity Buildings for both programs).



Key Project Metrics

- ◆ Public Private Partnership / P3
- ◆ Integrated Project Delivery

Constraints



- ◆ Fixed Client Budget
- ◆ Fixed Schedule
- ◆ Predeveloped Site with Existing Building
- ◆ Adjacent to a Wetland
- ◆ Historic Oak Trees
- ◆ Archeological Issues
- ◆ Temporary Beach Volleyball Courts



Design Option

- ♦ To create this facility, the **site was reimagined** as a vibrant and inviting environment.
- ♦ The design had to respond to the **surrounding context**, including an existing building and an adjacent wetland.
- ♦ The **existing** pool and volleyball courts had to be removed to make way for the new Athletic Complex.



Design Option



Budget Options

	Two Buildings Scheme “A”		One Building Scheme “B”		
Design & Engineering	\$18.50	\$555,000	\$18.50	\$555,000	\$0
Preconstruction	\$2.00	\$60,000	\$2.00	\$60,000	\$0
General Conditions	\$14.00	\$420,000	\$14.00	\$420,000	\$0
General Requirements	\$5.00	\$150,000	\$5.00	\$150,000	\$0
Sitework	\$9.33	\$580,000	\$9.33	\$280,000	\$0
Structure	\$42.33	\$1,269,815	\$33.26	\$997,815	-\$272,000
Exterior Closure	\$3.87	\$116,010	\$3.87	\$116,010	\$0
Roofing	\$4.77	\$143,000	\$6.13	\$184,000	\$41,000
Interior Finishes	\$12.89	\$386,750	\$12.89	\$386,750	\$0
Equipment & Furnishings	\$3.00	\$90,000	\$3.00	\$90,000	\$0
Mechanical	\$37.50	\$1,125,000	\$37.50	\$1,125,000	\$0
Electrical	\$37.17	\$1,115,000	\$37.17	\$1,115,000	\$0
AV Equipment & Install	\$0.34	\$10,200	\$0.34	\$10,200	\$0 Owner Provided Budget
Moveable Storage Shelving	\$45.00	\$1,350,000	\$45.00	\$1,350,000	\$0 Owner Provided Budget
Construction Totals	\$237.86	\$7,135,775	\$227.99	\$6,839,775	-\$296,000.00
Subtotal		\$7,135,775		\$6,839,775	
Owner Budget (Per Facilities Program)		\$6,845,000		\$6,845,000	
Delta		-\$290,775		\$5,225	
	Two Buildings Scheme “A”		One Building Scheme “B”		

Risk Matrix

Coordination

- ♦ Project GMP Set at 60% Design in lieu of 100% due to Schedule
- ♦ Long Lead Materials Identified

Risk Identification and Impact Assessment							Risk Response					
ID	Risk Evaluation Category	Risk Statement	Impact Value \$	Risk Owner	Risk Probability	Risk Impact	Risk Response	Mitigation Cost In Estimate	Mitigation Summary	Remaining Exposure	Risk % to Carry	Contingency Cost to Carry
1.00	Pre-Construction	Incomplete design package to provide full GMP. Risk exposure assumes 3% cost of work	\$ 1,230,000.00	Duncan	Possible	Major	2-Plan Risk Response			\$ 1,230,000.00	50%	\$ 615,000.00
4.00	Pre-Construction	One Concrete Bid, risk that they are off by more than 10%	\$ 150,000.00	Ware/Duncan	Possible	Moderate	2-Plan Risk Response			\$ 150,000.00	25%	\$ 37,500.00
5.00	Pre-Construction	Masonry Scope only had two bids and a large gap between them	\$ 400,000.00	Ware/Duncan	Possible	Major	2-Plan Risk Response	\$ 150,000.00		\$ 250,000.00	50%	\$ 125,000.00
17.00	Pre-Construction	Electrical scope only two bids and large gap	\$ 500,000.00	Ware/Duncan	Possible	Moderate	2-Plan Risk Response			\$ 500,000.00	25%	\$ 125,000.00
18.00	Pre-Construction	Sitework wide spread in bids and carrying low bidder	\$ 450,000.00	Ware/Duncan	Likely	Moderate	2-Plan Risk Response			\$ 450,000.00	50%	\$ 225,000.00
19.00	Design	Structural support of classroom demising walls		RDB	Unlikely	Minor	1-Watch			\$ -	0%	\$ -
20.00	Planning & Development	Electrical gear and Mechanical Equipment lead times	\$ 150,000.00	Electric and HVAC subcontractors	Possible	Critical	3-Plan Risk Response and Implement		Current GMP includes alternate gear design. Need authorization to release			
21.00	Pre-Construction	Material Escalation - 1% of COW	\$ 418,839.40	Ware/Duncan	Possible	Major	2-Plan Risk Response			\$ 418,839.40	50%	\$ 209,419.70
22.00	Pre-Construction	Buyout Scope Gaps - 1% COW	\$ 418,839.40	Duncan/PM	Possible	Major	2-Plan Risk Response			\$ 418,839.40	50%	\$ 209,419.70

Structural System Analysis

- ♦ Analyzed Tilt CMU Vs & Steel Structure
- ♦ Exterior of the Building is Arch. CMU with standard CMU and Veneer at the front of the Building



CMU

Initial Cost



Material Availability




Overall Schedule



Durability



Sustainability




Tilt-Up Panels and Structural Steel



Final Design



Coordination



Tools Commonly Used

- BIM / Revit
- Clash Detection / VDC
- Team Coordination Meetings

End Results

- ◆ On Budget
- ◆ Ahead of Schedule
- ◆ Happy Client



End Results



End Results



End Results



End Results



End Results



End Results




End Results



End Results



Awards



Summary



Consider an **Integrated Project Delivery Approach**



Get Market Input Early in Design Planning Stages



Communicate Openly



Be **Innovative**

Q & A

